Serial No.	Items of work	Unit	Quantity	Rates to be quoted	
				In figures	In words
	First Floor.				
1	Burnt brick in sand mortar	C.ft.	7,747		
2	R. C. Circular pillars 1½′ dia., including caps and bases with plastering, etc., complete ..	R.ft.	108		
3	Teakwood doors 3½″×5″ frames with 1½″ thick shutters bottom ½ panelled and ⅝ glazed with rectangular ventilator at top complete with brass fittings	S.ft.	320		
4	Teakwood doors 3″×4″ frame work shutters 1¼″ thick with glasses, with rectangular ventilators at top with brass fittings, etc., complete ..	,,	224		
5	Teakwood windows 3½″×5″ frame shutters 1¼″ thick, glazed with rectangular ventilator at top with iron bars, brass fittings, etc., complete	,,	686		
6	R. C. Ventilators, as per design, including fixing, etc.	,,	63		
7	R. C. C. partition wall, 9″ thick including plastering with cement, etc., complete	,,	2,538		
8	R. C. Beams and slabs finished complete ..	C.ft.	1,005		
9	R. C. and brick terrace 6″ thick with 2 courses of flat tiles with plastering, etc., complete ..	Sqrs.	50·74		
10	Flooring with cement 1½″ thick finished with topping of red cement, etc., complete or any other kind of approved flooring	,,	41·70		
11	Tested R. S. girders as per specifications including hoisting and fixing	Cwt.	123·3		
12	Boxing the girders, with cement mortar and terrace bricks reinforced with steel net tied alround	R.ft.	252		
13	Plastering with sand mortar	Sqrs.	80·22		
14	White and cream colour washing 2 coats ..	,,	80·22		
15	Silicate or any other approved kind of painting to doors and windows 2 coats	,,	24·35		
16	Ornamental pipe hand railings as per design ..	R.ft.	153		
17	Ornamental parapet wall 2½″ high, including plastering, etc.	,,	133		
18	Ornamental parapet wall 1½′ high complete ..	,,	608½		
19	Providing rain water and down take pipes ..	Lumpsum			
20	Ceiling ornamentations	do			
21	Clearing site and levelling ground	do			

N. SARABHOJA,
Executive Engineer.

ANJANAPUR DIVISION.

Tender Notice dated 3rd May 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Anjanapur Division, up to 12 NOON on Monday the 4th July 1938, for constructing a Mosque at Anjanapur, Shikarpur Taluk, Shimoga District.

2. Tenders in the prescribed form should be addressed to the Executive Engineer, Anjanapur Division, in a sealed cover and superscribed as "Tender for constructing a Mosque at Anjanapur." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 175 (rupees one hundred and seventy-five only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest. On acceptance of the tender, a sum equal to ten per cent of the estimated cost will have to be deposited as security deposit.

4. The tenders will be opened in the presence of such tenderers who wish to be present on Monday the 4th July 1938 at 2 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Anjanapur, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 5.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer or his representatives. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of October 1938, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs.....per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over. The monthly rate of progress should be mentioned in the tender.

18. In all matters of disputes of any kind not specifically provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in such transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—*(a)* The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slumps pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for constructing a Mosque at Anjanapur, Shikarpur Taluk.

No.	Items of work	Per	Quantity	Rate	Cost
			Rs. a. p.		Rs.
1	Earthwork excavating foundations	C.yd.	40	..	
2	Stone jolly in chunnam mortar	C.ft.	383	..	
3	Size stone in mud with bond stones 6″ apart	,,	940	..	
4	Burnt brick in mud-superstructure	,,	1,065	..	
5	Burnt brick in mortar (chunnam)	,,	527	..	
6	Preparing and fixing cement concrete slabs with cement plastering complete 6″ thick	,,	135	..	
7	Reinforced cement concrete for *Mihrab* portion for arch work	,,	96	..	
8	Madras pucca terrace with plastering, etc., complete	Sqrs.	6.34	..	
9	Archwork burnt brick in chunnam mortar	C.ft.	98		
10	Providing perforated work above windows	S.ft.	25	..	
11	Deep cement pointing	Sqrs.	1.67	..	
12	Chunnam plastering (brick walls)	,,	30.14	..	
13	Whitewashing two coats	,,	30.14	..	
14	Rolled steel joists and beams including fixing and boxing in cement mortar complete	Cwt.	41.78	..	
15	Teakwood doors $3\frac{1}{2}'' \times 4\frac{1}{2}''$ section, with battened shutters, hinges, bolts, etc., complete with chocolate paint	S.ft.	77	..	
16	Teakwood windows with battened shutters and fixtures complete with chocolate paint including iron bars $\frac{3}{4}''$ dia. 4″ apart	,,	88	..	
17	Constructing parapet wall with ornamental pillasters at end including cornice 3″ thick, etc.	R.ft.	$122\frac{1}{4}$	..	
18	Providing cornice 9″ thick	R.ft.	132	..	
19	Providing ornamental phinials	Each	4	..	
20	Flooring with 3″ surki concrete and $1\frac{1}{2}''$ cement concrete with $\frac{1}{2}''$ cement plaster at top and smoothening with red ochre	Sqrs.	5·56	..	
21	Providing spouts on terrace portion 3″ to 4″ dia. (for rain water)	Each	15		
22	Providing seat for prayer	L. S.		..	
23	Providing cistern in front	L. S.		..	
24	Providing drain alround	L. S.			
25	Jungle clearing and site clearing	L. S.	..		
26	Extra foundation (required in side-long ground)	L. S.	..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, MARKONAHALLI RESERVOIR DIVISION, MARKONAHALLI.

Notification dated the 27th May 1938.

Notice is hereby given that sealed quotations will be received by the undersigned up to 4 P.M. on 20th June 1938 for the supply of 400 tons of hard fuel and 100 tons of soft fuel required for the Government work. The size of the billets to be 3′ long and 3″ to 6″ in diameter.